App F IX 4

Previous References

1944 Municipal Mt File No 81-44
Serial Nos 7, 8

Later References

GENERAL AND REVENUE SECRETARIAT

Serial Nos 2

Part B for Sejpur

SUBJECT

Re: Issuing of cement concrete bricks for construction of Manhole & rate There of ~~DP 44~~ — in B'Use of Drainage scheme

The D.P.H
.. Chief Engr. Irrigation
.. Comptroller to go out

Lr no 2611-14 dated 29 9-44
Proposal approved.

M
L&II

From the D P H

No C 81-1622 - 13/8/46

Requests approval to 1) The use of cement concrete bricks (1 3 6) for all manholes to be constructed hereafter, 2) the payment of a rate of Rs 1-4-0 per cubic foot of cement concrete construction and 3) The construction of manholes with ordinary burnt bricks in cement in place of wire cut bricks at rates noted by him

It is stated that the Chief Engineer for Irrigation has also agreed to the changes proposed. The report is subject to approval and the proposal is for orders

Ma The proposals have been 17/8 agreed to by the Chief Engineer for Irrigation (vide Flag D)

The arrangement is stated to have been brought into force already for the last six months by way of is adopted due to non-availability of wire cut bricks in the area

If required, the Director's proposals may be accepted

Law Secy
17/8/46

SEC'Y LAW DEPT
22 AUG 1944
GOVT OF MYSORE

A.70.

Continuation Sheet | File No / Current No | of | Page

The Min Approval may be approved

Mrs Lee 17-8-44

OFFICE OF THE MINISTER FOR L S G & P H
Date 18 8 1944
No 1388

Mrs Lee 16 8 44

Mrs Lee 16 & 22-9

Dft ltr 18/8/44

Dft letter is submitted Mrs 21/8

The draft requires to be amplified Mrs 28/8/44

A draft go as submitted, as per instructions Mrs 13/9

Revised draft submitted Mrs 22/9/44

To,

The D P H
The Chief Engineer for irrigation
The Comptroller
& 28 11 - 14 & 28 - 9 - 44
Same claims the proposal Mrs 8/11

HLSW447 976/

GOVERNMENT OF MYSORE

PUBLIC DEPARTMENT OF/ HEALTH

GEN & REV SECR 10 AUG 1944 L S G BRANCH

No C81-1622
Encl 2. Copies of letter
1. Data sheet
1 Design & calculation
1 Estimate & cost report

DR P PARTHASARATHY L M S B S SC (Mad) L R C P & S (Edin) D T M (Lond) D P H (Camb)
Director of Health

~~BACTERIOLOGIST TO GOVERNMENT (Munich) (Dresden)~~
~~(Berlin)~~
~~DIRECTOR~~

BUREAU OF MATERNITY CHILD AND OTHER WELFARE WORKS
Vani Vilas Centre Vani Vilas Road
Bangalore
Mysore (S India) dated 31d August 1944

9/8/44

To

The Secretary to Government,
~~Law~~ Education Department,
Bangalore

for SECRETARY

Sir,

Subject - Constructing manholes with precast cement concrete

I have the honour to state that the Special Officer in his letter No 51 dated 9th August 1943 submitted proposl for 1) substituting burnt bricks for the construction of manholes etc 2) the reduction of the weight of cast iron manhole frame and cover from 4 cwts to 2 cwts 3) and the payment of rates for different depths of manholes to the contractors as per data sheet instead of tendered rates The matter was referred to the Chief Engineer and he in his letter No 13237 dated 7 12 43 intimated that proposal of the Special Officer may be approved so as to continue the work without interruption He however suggested certain modifications to be effected, after investigation, in future work Copies of the letters of the Special Officer and the Chief Engineer with enclosures are attached for the information of Government

In accordance with the suggestions of the Chief Engineer, the Special Officer sent the data, design and calculation sheets, estimate of cost andreport etc , for constructing mannoles of 4,8 and 12 feett depths in precast cement concrete bricks TheChief Engineer to whom the matter was referred for opinion intimates in his letter No 695/I dated 8th June 1944 that precast cement concrete bricks of 1 3 6 proportion may be used for corstructing manholes in preference to the wire cut bricks He has also approved the design and has stated that the rate of Rs 4 per cubic feet of cement concrete construction may be included in the current schedule

I request you to be so good as to obtain and covey approval of Government to the use of cement concrete bricks (1 3 6) for all manholes to be constructed hereafter and to the rate of Rs 1-4-0 per cubic foot of cement concrete construction Approval may also be communicated to the construction of manhole, with ordinary burnt bricks in cement in place of wire cut bricks, due to nonavailability of wire cut bricks and to the payment for them as per data sheet enclosed

Copies of letter No 229 dated 4th February 1944 of the Special Officer and No 695 dated 8 6 44 of the Chief Engineer with enclosures are also enclosed

Put to with a D/L letter affirming the proposal for rates

16/8 BsN

I have the honour to be,
Sir,
Your most obedient servant,

Director of Public Health

16/8

(1) Proceedings of the first M-W-H 165 / Laboratory Type

Read

3rd Letter no C 81—1622 dated the
Superintending Engineer from the Director
of Public Health requesting approval,
in connection with the Improvement
scheme, (1) to the use of Cement
Concrete bricks (1·3·6) for all
manholes to be constructed hereafter,
as to the payment of a rate
of Rs 1/4/- per cubic foot of
Cement Concrete construction and (3)
the contracts of manholds with ordinary
burnt bricks in cement in place
of cut bricks — stone which are
not available at present for the
purpose for them as per data sheet
enclosed instead of tenders called
Engineer for Transportation and that the Chief
the matter was agreed to the adoption
of the above arrangements of rates
under No. L 2811-44/HH 81-44-6
D29-9-44 are appro
above proposals

To the Secy to H.M. for the
information of the Minister

PROCEEDINGS OF THE GOVERNMENT OF HIS HIGHNESS THE MAHARAJA OF MYSORE

Extra 4

Read -

Letter No C.61-1622 dated the 3rd August 1944, from the Director of Public Health, requesting approval, in connection with the Bangalore City Drainage Scheme, - (1) to the use of cement concrete bricks(1 3 6) for all manholes to be constructed hereafter, (2) to the payment of a rate of Rs. 1/4/- per cubic foot of cement concrete construction and (3) the construction of manholes xxxx with ordinary burnt bricks in cement in - place of xxx wire cut bricks, which are not available at present and to the payment for them as per data sheet enclosed instead of tendered rates and adding that the Chief Engineer for Irrigation who was consulted in the matter has agreed to the adoption of the above arrangements and rates

---

ORDER NO. 2811-14/Jud 81-44-8

Dated, 29th Sept 1944

The above proposals are approved

For Secretary to Government
Law Department.

To

The Director of Public Health with records.
The Chief Engineer for Irrigation
The Comptroller to Govt. & Municipal Commissioner, Bangalore City.

TLS/5